

Franklin Manor Sanitary Sewer Rehabilitation

Project Description:

The projects consists of rehabilitation approximately 11,000 lineal feet of 8-inch and 300 lineal feet of 6-inch diameter vitrified clay sanitary sewer pipe using a cured-in-place, no-excavation pipe renovation process

The works includes, but is not limited to, the following:

- Perform a pre-insertion video inspection of the existing sanitary sewer pipe.
- Clean the existing pipe and/or remove obstructions, as needed.
- Furnish a pump bypass line to provide continuous sewage flow around the sections of pipe designated for insertion of new pipe.
- Furnish and install a cured-in-place pipe (CIPP) within the existing vitrified clay pipe, including all work needed to repair any and all broken and/or depressed portions of the sewer in order to provide an uniform slope between manholes.
- Following installation and curing of the CIPP, re-establish access to all service laterals.
- Cleanup the entire work area.
- The work includes furnishing of all labor, material and equipment and the performing of all operations in connection with this installation, complete with all appurtenances as described herein, and as shown on the Drawings and as needed to provide complete and usable facilities.

Bids for the project were opened on June 29th and the Township voted to accept the proposal of United Survey, Inc. on July 5th. The project should begin in August.